Comhairle Contae Chill Dara
Kildare County Council

Date: 23rd April 2026
Our Ref: ED/1336

Joseph Heffernan,
c/o Alan Meredith,
Old Grange,
Monasterevin,
Co. Kildare.

RE: Application for a Declaration of Exempted Development under Section 5 of Planning and Development Act 2000 (as amended) for development at Tully East, Kildare, Co. Kildare.

Dear Sir/Madam,

I refer to your correspondence received on 19th March 2026 in connection with the above.

Please find attached declaration made under Section 5 of Planning and Development Act 2000 (as amended) in this regard.

Yours sincerely,

PP
Senior Executive Officer,
Planning Department.

Comhairle Contae Chill Dara
Kildare County Council

Declaration of Development & Exempted Development under Section 5 of the Planning and Development Act 2000 (as amended).

ED/1336

WHEREAS a question has arisen as to whether a proposed agricultural building for storage, shed, barn not exceeding 300sq.m. and will not be used for housing animals and storing effluent at Tully East, Kildare, Co. Kildare, is exempted development

AS INDICATED on the plans and particulars received by the Planning Authority on 19th March 2026

AND WHEREAS Joseph Heffernan requested a declaration on the said question from Kildare County Council,

AND WHEREAS Kildare County Council as the Planning Authority, in considering this application for a declaration under Section 5 of the Planning and Development Act 2000 (as amended), had regard to;

(a) Planning and Development Act 2000 (as amended) and
(b) Planning and Development Regulations 2001 (as amended);

AND WHEREAS Kildare County Council has concluded that the development comprises works to which the provisions of the following applies:

(a) Sections 2, 3, 5 of the Planning and Development Act 2000 (as amended);
(b) Articles 6 and 9 of the Planning and Development Regulations 2001 (as amended); and
(c) Schedule 2, Part 3, Class 9 of the Planning and Development Regulations 2001 (as amended); and
(d) The nature, extent and purpose of the works

NOW THEREFORE Kildare County Council, in exercise of the powers conferred on it by Section 5(2)(a) of the Planning and Development Act 2000 (as amended), hereby decides that a proposed agricultural building for storage, shed, barn not exceeding 300sq.m. and will not be used for housing animals and storing effluent at Tully East, Kildare, Co. Kildare ***IS development and IS EXEMPTED DEVELOPMENT pursuant to Sections 2, 3 and 5 of the Planning and Development Act 2000 (as amended); Articles 6 and 9 of the Planning and Development Regulations 2001 (as amended) and Schedule 2, Part 3, Class 9 of the Planning and Development Regulations 2001 (as amended).***

Comhairle Contae Chill Dara
Kildare County Council

Please note that any person issued with a declaration under subsection 2(a) of the Planning and Development Act 2000 (as amended) may on payment to the Coimisiún of the prescribed fee, refer a declaration to An Coimisiún Pleanála within 4 weeks of the issuing of the decision.

23rd April 2026

PP
Senior Executive Officer,
Planning Department.

KILDARE COUNTY COUNCIL

PLANNING & STRATEGIC DEVELOPMENT DEPARTMENT

Section 5 referral & declaration on development & exempted development

Planning & Development Act 2000 (as amended)

Reference No. ED/1336

Name Of Applicant(s):	Joseph Heffernan
Address Of Development:	Tully East, Kildare, Co. Kildare.
Development Description:	Proposed agricultural building for storage, shed, barn not exceeding 300sq.m. and will not be used for housing animals or storing effluent.
Due date	16/04/2026

Introduction

This is a request for a **DECLARATION** under Section 5(1) of the Planning and Development Act 2000 (as amended) to establish whether under Section 5 of the Act the works include:

"Proposed agricultural building Type 4".

Site Location

The site is located in the rural townland of Tully East, c. 3km south of the M7 motorway south of Kildare Town. The site is a greenfield site currently in agricultural use. There is an existing residential dwelling adjoining the site to the north and a farmyard and associated dwelling to the south.



Site Location & Context (approximate site location denoted by red star)

Description of Proposed Development

The proposed development is described as follows:

"Proposed agricultural building for storage, shed, barn not exceeding 300 sqm and will not be used for housing animals or storing effluent."

Planning History

Application site

23/60081 - Permission refused to Lorraine Deering for construction of a single storey part storey and a half type dwelling, new wwts and polishing filter, new recessed entrance at location of existing entrance, detached domestic garage/shed and all ancillary works. Permission refused for the following reason:

Permission is REFUSED for the following reasons:

1. The site is not considered suitable for a domestic wastewater treatment system as proposed on the grounds that:
(a) It is highly likely, given past experience in this area, that the water table would be less than 500 mm below ground level during the winter months. Therefore At least 500mm depth of unsaturated self-draining sub-soil to the water table and/or bedrock beneath the proposed DWWTP may not be available as required in Section 6.4 table 6.3 of the Environmental Protection Agency Code of Practice.
(b) The proposals as indicated in the application have been noted however, a raised mound is not considered to be site improvement works and the presence of peat soils underlain by marl clay/chalk in the proposed percolation area are not suitable for the treatment or the disposal of treated waste water due to poor percolation and the consequent risk of pollution of waters and the risk to public health.

The proposal would therefore be prejudicial to human health, would be contrary to the provisions of Policy HO P27 of the Kildare County Development Plan 2023-2029 which requires applications to demonstrate, to the satisfaction of the Planning Authority that the proposed development site can accommodate an on-site wastewater treatment system in accordance with the Environmental Protection Agency Code of Practice for Wastewater Treatment Systems for single houses (2021), the County Kildare Groundwater Protection Scheme, and any other relevant documents/legislation as may be introduced during the Plan period and, would therefore, be contrary to the proper planning and sustainable development of the area.

20/273 - Permission refused to Bernard Snell for construction of a bungalow, new entrance gate, double garage, private well, effluent treatment system. Permission refused for the following reasons:

Planning Permission refused for the following reasons:

1. Policy RH2 of the Kildare County Development Plan 2017 – 2023 requires that all applicants for housing in the rural area demonstrate compliance with the criteria set out in Tables 4.3(a) and (b) of the Kildare County Development Plan 2017 – 2023. Having regard to the documentation received in relation to this planning application, the Applicant has not sufficiently demonstrated compliance with a category of the local need criteria. Accordingly, the proposed development would materially contravene Policy RH2 of the Kildare County Development Plan 2017 – 2023 and would therefore be contrary to the proper planning and sustainable development of the area.

2. Policy RH9 (iii) and (v) of the Kildare County Development Plan 2017-2023 seeks to ensure that, notwithstanding compliance with the local need criteria, applicants comply with all other normal siting and design considerations, including the protection of features that contribute to local attractiveness, such as trees and hedgerows and the ability to provide safe vehicular access to the site without the necessity to remove extensive stretches of native hedgerow and trees. The proposed development includes removal of approximately 75m of native hedgerow and trees, which is considered an excessive quantity of hedgerow removal, which indicates the site is unsuitable for the proposed development. The extensive removal of roadside hedgerow would seriously injure the rural and visual amenities of the area, would negatively affect the rural character of the area and would negatively impact on local biodiversity. The proposed development would contravene policy RH9 (iii) and (v) of the Plan and would therefore be contrary to the proper planning and sustainable development of the area.

22/445 - Permission refused to Lorraine Deering for construction of a single storey, part storey and a half type dwelling and wwts. Permission refused for the following reason:

Permission is REFUSED for the following reason:

1. The site is not considered suitable for a domestic wastewater treatment system as proposed on the grounds that it is highly likely, given past experience in this area, that the water table would be less than 500 mm below ground level during the winter months. Therefore, at least 500mm depth of unsaturated self-draining sub-soil to the water table and/or bedrock beneath the proposed DWWTP may not be available as required in Section 6.4 Table 6.3 of the EPA Code of Practice, 2021. Furthermore, the presence of peat soils underlain by marl clay/chalk in the proposed percolation area are not suitable for the disposal of treated waste water due to poor percolation and the consequent risk of pollution of waters and the risk to public health. To permit the proposed development would be prejudicial to public health and would therefore be contrary to the proper planning and sustainable development of the area.

Relevant Legislative Background

Planning and Development Act 2000 (as amended)

Section 2(1)

'works' includes any act or operation of construction, excavation, demolition, extension, alteration, repair or renewal and, in relation to a protected structure or proposed protected structure, includes any act or operation involving the application or removal of plaster, paint, wallpaper, tiles or other material to or from the surfaces of the interior or exterior of a structure.

Section 3(1)

In this Act, 'development' means, except where the context otherwise requires, the carrying out of any works on, in, over or under land or the making of any material change in the use of any structures or other land.

Class 9 of Part 3 of Schedule 2 of the Planning and Development Regulations, 2001 as amended

Section 5(7) EIA Screening

The proposed development is not specified in Part 2 of Schedule 5 of the Planning and Development Regulations 2001(as amended). In any event, it is considered, having regard to nature, size and location, the proposed development would not be likely to have significant effects on the environment. Therefore, EIA is not required.

Planning and Development Regulations 2001 (as amended)

Article 6(3)

Subject to article 9, in areas other than a city, a town or an area specified in section 19(1)(b) of the Act or the excluded areas as defined in section 9 of the Local Government (Reorganisation) Act, 1985 (No. 7 of 1985), development of a class specified in column 1 of Part 3 of Schedule 2 shall be exempted development for the purposes of the Act, provided that such development complies with the conditions and limitations specified in **column** 2 of the said Part 3 opposite the mention of that class in the said column 1.33

Class 9 of Part 3 of Schedule 2 of the Planning and Development Regulations, 2001, as amended, *is relevant:*

CLASS 9	Assessment
Column 1 Description of Development Works consisting of the provision of any store, barn, shed, glass-house or other structure, not being of a type specified in class 6, 7 or 8 of this Part of this Schedule, and having a gross floor space not exceeding 300 square metres.	The works comprise an agricultural shed with a gross floor area not exceeding 300sqm. **Complies.**
Column 2 Conditions and Limitations 1. No such structure shall be used for any purpose other than the purpose of agriculture or forestry, but excluding the housing of animals or the storing of effluent.	1. The shed will be used for storage purposes and will not be used for housing of animals or storing effluent **Complies**.
2. The gross floor space of such structures together with any other such structures situated within the same farmyard complex or complex of such structures or within 100 metres of that complex shall not exceed 900 square metres gross floor space in aggregate.	2. While there is a cluster of agricultural buildings on an adjoining site, it does not appear that there are other agricultural structures within 100m of the proposal **Complies**.
3. No such structure shall be situated within 10 metres of any public road.	3. The structure would be located more than 200m from the public road. **Complies**.
4. No such structure within 100 metres of any public road shall exceed 8 metres in height.	4. The height of the structure would be 7.9m at its highest point. **Complies.**
5. No such structure shall be situated within 100 metres of any house (other than the house of the person providing the structure) or other residential building or school, hospital, church or building used for public assembly, save with the consent in writing of the owner and, as may be appropriate, the occupier or person in charge thereof.	5. The structures would not be located within 100meters of <u>any</u> house. **Complies.**

6. No unpainted metal sheeting shall be used for roofing or on the external finish of the structure.	6. The cladding would be green or grey **Complies**

Assessment

The proposal falls under *Class 9 of Part 3 of Schedule 2 of the Planning and Development Regulations, 2001, as amended* and that it complies with the conditions and limitations therein as demonstrated in the preceding Table 1

Conclusion

Having regard to:

- Sections 2, 3, 5 of the Planning and Development Act 2000 (as amended);
- Articles 6 and 9 of the Planning and Development Regulations 2001 (as amended);
- Schedule 2, Part 3, Class 9 of the Planning and Development Regulations 2001 (as amended); and
- The nature, extent and purpose of the works;

it is considered that the proposed works **constitutes development** as defined in Section 3(1) of the Planning and Development Act 2000 (as amended) and **is exempted development** as defined by the Planning and Development Act 2000 (as amended) and the Planning and Development Regulations 2001 (as amended).

Recommendation

It is recommended that the applicant be advised that the development as described in the application *is development and is exempted development.*



Executive Planner
17/04/2026



Martin Ryan
Senior Executive Planner
23/04/2026

Declaration of Development & Exempted Development under

Section 5 of the Planning and Development Act 2000 (as amended)

WHEREAS a question has arisen as to whether a proposed agricultural building "Type 4"

AS INDICATED on the plans and particulars received by the Planning Authority on 19/03/2026

AND WHEREAS Joseph Heffernan requested a declaration on the said question from Kildare County Council,

AND WHEREAS Kildare County Council as the Planning Authority, in considering this application for a declaration under Section 5 of the Planning and Development Act 2000 (as amended), had regard to;

(a) Planning and Development Act 2000 (as amended); and
(b) Planning and Development Regulations 2001 (as amended);

AND WHEREAS Kildare County Council has concluded that the proposal comprises of development to which the provisions of the following applies:

(a) Sections 2, 3, 5 of the Planning and Development Act 2000 (as amended);
(b) Articles 6 and 9 of the Planning and Development Regulations 2001 (as amended);
(c) Schedule 2, Part 3, Class 9 of the Planning and Development Regulations 2001 (as amended); and
(d) The nature, extent and purpose of the works

NOW THEREFORE Kildare County Council, in exercise of the powers conferred on it by Section 5(2)(a) of the Planning and Development Act 2000 (as amended), hereby decides that -

A proposed agricultural building for storage, shed, barn not exceeding 300 sqm and will not be used for housing animals or storing effluent

IS development and IS EXEMPTED development pursuant to Section 2, 3 and 5 of the Planning and Development Act as amended and Article 6, Article 9 and Schedule 2, Part 3, Class 9 of the Planning and Development Regulations as amended.

Please note that any person issued with a declaration under Section 5 of the Planning and Development Act 2000 (as amended) may on payment to the Board of the prescribed fee, refer a declaration to An Bord Pleanála within 4 weeks of the issuing of the decision.

Signed: _____

Appendix 1: Appropriate Assessment Screening

APPROPRIATE ASSESSMENT SCREENING REPORT
AND
DETERMINATION

(A) Project Details	
Planning File Ref	ED1336
Applicant name	Joseph Heffernan
Development Location	Tully East, Kildare
Site size	1.78 ha
Application accompanied by an EIS (Yes/NO)	No
Distance from Natura 2000 site in km	c.4.3km from River Barrow and River Nore SAC
Description of the project/proposed development – AGRICULTURAL BUILDING	

(B) Identification of Natura 2000 sites which may be impacted by the proposed development			
			Yes/No If answer is yes, identify list name of Natura 2000 site likely to be impacted.
1	**Impacts on sites designated for freshwater habitats or species.** Sites to consider: River Barrow and Nore, Rye Water/Carton Valley, Pollardstown Fen, Ballynafagh lake	*Is the development within a Special Area of Conservation whose qualifying interests include freshwater habitats and/or species, or in the catchment (upstream or downstream) of same?*	**NO**
2	**Impacts on sites designated for wetland**	*Is the development within a Special Area of Conservation whose*	**NO**

	habitats - bogs, fens, marshes and heath. Sites to consider: River Barrow and Nore, Rye Water/Carton Valley, Pollardstown Fen, Mouds Bog, Ballynafagh Bog, Red Bog, Ballynafagh Lake	*qualifying interests include wetland habitats (bog, marsh, fen or heath), or within 1 km of same?*	
3	**Impacts on designated terrestrial habitats.** Sites to consider: River Barrow and Nore, Rye Water/Carton Valley, Pollardstown Fen, Ballynafagh Lake	*Is the development within a Special Area of Conservation whose qualifying interests include woodlands, dunes or grasslands, or within 100m of same?*	**NO**
4	**Impacts on birds in SPAs** Sites to consider: Poulaphouca Resevoir	*Is the development within a Special Protection Area, or within 5 km of same?*	**NO**

Conclusion:
If the answer to all of the above is **No**, significant impacts can be ruled out for habitats and bird species.
No further assessment in relation to habitats or birds is required.
If the answer is **Yes** refer to the relevant sections of **C.**

(G) SCREENING CONCLUSION STATEMENT *Selected relevant category for project assessed by ticking box.*		
1	AA is not required because the project is directly connected with/necessary to the conservation management of the site	
2	No potential significant affects/AA is not required	**X**
3	Significant effects are certain, likely or uncertain. Seek a Natura Impact Statement Reject proposal. (Reject if potentially damaging/inappropriate)	
Justify why it falls into relevant category above (based on information in above tables)		
Location, scale, distance from Natura 2000 sites = no impact on integrity of Natura 2000 sites		
Name:	C.Dockery	
Position:	Executive Planner	
Date:	17/04/2026	

COMHAIRLE CONTAE CHILL DARA

KILDARE COUNTY COUNCIL

Director of Services Order

I, Alan Dunney, Director of Services of Planning, Enterprise & Economic Development, by the powers conferred on the Chief Executive of Kildare County Council under Section 151 of the Local Government Act 2001, as amended by the Local Government Reform Act 2014, and which powers are delegated to me pursuant to Section 154 of the Local Government Act 2001 (as amended) by Chief Executive's Order number: CE63325, do hereby make the following Order:

ORDER NO: DO65206 **Section:** Planning

SUBJECT: ED/1336
Joseph Heffernan, c/o Alan Meredith, Old Grange, Monasterevin, Co. Kildare Exempt Development application as to whether a proposed agricultural building for storage, shed, barn not exceeding 300sq.m. and will not be used for housing animals and storing effluent at Tully East, Kildare, Co. Kildare is exempted development.

SUBMITTED: File Ref. ED1336 with recommendation from the Senior Executive Planner and reports from the Council's Technical Officers.

ORDER: **I hereby order the following** Kildare County Council, in exercise of the powers conferred on it by Section 5(2)(a) of the Planning and Development Act 2000 (as amended) hereby decides that the proposed development is exempted development.

MADE THIS 23rd DAY

OF April YEAR 2026

SIGNED: _____

DIRECTOR OF SERVICES

Comhairle Contae Chill Dara
Kildare County Council

Date: 19th March 2026
Our Ref: ED/1336

Joseph Heffernan,
c/o Alan Meredith,
Old Grange,
Monasterevin,
Co. Kildare.

RE: Application for a Declaration of Exempted Development under Section 5 of Planning and Development Act 2000 (as amended) for development at Tully East, Kildare, Co. Kildare.

Dear Sir/Madam,

I acknowledge receipt of your application for a Declaration of Exempted Development under Section 5 of Planning and Development Act 2000 (as amended) received on 19th March 2026 in connection with the above.

Yours sincerely,

pp Norma O'Connor

Senior Executive Officer,
Planning Department.

Kildare County Council

Declaration of Exempt Development under Section 5,

of the Planning and Development Act 2000 as amended

Incomplete application forms will be deemed invalid and returned

All responses must be in block letters

Section 1	Details of Applicants

1. Name of Applicant(s) A. Surname. Joseph Forenames. HEFFERNAN
Phone No [redacted] Fax No.....
2. Address Maplewood, Oonagnew, Kildare, Co. Kildare

Section 2	Person/Agent acting on behalf of applicant (if applicable)

1. Name of Person/Agent: Surname. Meredith Forenames. Alan
Phone No [redacted] Fax No. —
2. Address. Old Grange, Monasterevin, Co. Kildare

Section 3	Company Details (if applicable)

1. Name of Company .....
Phone No..... Fax No.....
2. Company Reg. No.....
3. Address.....

Section 4	Details of Site

1. Planning History of Site. None
2. Location of Proposed Development. Tully East, Kildare, Co. Kildare
3. Ordnance Survey Sheet No. 3718-C
4. Please state the Applicants interest in the site ..... Owner
5. Please state the extent of the proposed development. Proposed Agricultural building "Type 4"

Kildare County Council
Planning Department
19 MAR 2026
RECEIVED

6. Under what Section of the Planning and Development 2000 as amended and/or what provision of the Planning and Development Regulations 2001 as amended is exemption sought *(specific details required)*

Type 4 Agricultural building not exceeding 300 sqm

7. Please give a detailed description of the Proposed Development *(Use separate page if necessary)*

Proposed Agricultural building For Storage, shed, barn not exceeding 300 sqm and will not be used for housing Animals or Storing effluent

Section 5	**The following must be submitted for a valid application**

		(Please Tick)
1.	Site Location Map (1:2500 Rural Areas) (1:1000 Urban Areas)	✓
2.	A Site Layout Plan (Scale 1:500) in full compliance with Article 23 of Planning and Development Regulations 2001 as amended	✓
3.	Drawings of the development (Scale 1:50) in full compliance with Article 23 of Planning and Development Regulations 2001 as amended	✓
4.	All drawings to differentiate between the original building, all extensions and proposed development	✓
5.	Fee of 80 Euro	✓


Section 6	**Declaration**

I, Joseph Heffernan certify that all of the above information is correct and I have submitted all the required documents as outlined at Section 6 above.

Signature: _____ Date: 19.03.2026

Kildare County Council
Planning Department
19 MAR 2026
RECEIVED

Planning Pack Map



Tailte Éireann

CENTRE COORDINATES:
ITM 673095,709034

PUBLISHED: 16/03/2026

ORDER NO.: 50524241_1

MAP SERIES: 1:2,500

MAP SHEETS: 3718-C

os ref

COMPILED AND PUBLISHED BY:
Tailte Éireann,
Phoenix Park,
Dublin 8,
Ireland.
D08F6E4

www.tailte.ie

Any unauthorised reproduction infringes Tailte Éireann copyright.

No part of this publication may be copied, reproduced or transmitted in any form or by any means without the prior written permission of the copyright owner.

The representation on this map of a road, track or footpath is not evidence of the existence of a right of way.

This topographic map does not show legal property boundaries, nor does it show ownership of physical features.


©Tailte Éireann, 2026.
All rights reserved.

OUTPUT SCALE: 1:2,500


CAPTURE RESOLUTION:
The map objects are only accurate to the resolution at which they were captured.
Output scale is not indicative of data capture scale.
Further information is available at:
www.tailte.ie; search 'Capture Resolution'

LEGEND:
To view the legend visit www.tailte.ie and search for 'Large Scale Legend'

North point



PROPOSED SITE PLAN
SCALE 1:500
SITE BOUNDARY
OUTLINE IN RED



PROPOSED SITE PLAN
SCALE 1:2000
SITE BOUNDARY
OUTLINE IN RED

Kildare County Council
Planning Department
19 MAR 2026
RECEIVED

THIS DRAWING IS ISSUED FOR PLANNING / DESIGN PURPOSES AND IS NOT INTENDED AS A CONSTRUCTION DRAWING


DO NOT SCALE FROM THIS DRAWING
ANY DISCREPANCIES AND DIMENSIONS IDENTIFIED BY CONTRACTOR / PROJECT MANAGER ARE TO BE REPORTED IMMEDIATELY TO THE CLIENT / ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK


DRAWING BY:
Alan Meredith
Architectural Services & Epa Percolation Testing
Old Grange, Monasterevin, Co. Kildare

FOR JOSEPH HEFFERNAN,
TULLY EAST,
KILDARE,
CO. KILDARE.


SCALE: 1/2000; 1/500	DATE MARCH 2026

PROJECT NO.	DRG. NO.	REV.
2026-03	P-02	1







SECTION A–A 1:125




WEST ELEVATION 1:125 (OPEN SECTION)



SOUTH ELEVATION 1:125



EAST ELEVATION 1:125



NORTH ELEVATION 1:125

Kildare County Council
Planning Department
19 MAR 2026
RECEIVED

PROPOSED AGRI BARN / STORE / SHED

TOTAL AGRI BARN / STORE / SHED AREA : 248 sqm (2669 sq ft)

THIS DRAWING IS ISSUED FOR PLANNING PURPOSES AND IS NOT INTENDED AS A CONSTRUCTION DRAWING

DO NOT SCALE FROM THIS DRAWING.
ANY DISCREPANCIES AND OMMISSIONS IDENTIFIED BY CONTRACTOR / PROJECT MANAGER ARE TO BE REPORTED IMMEDIATELY TO THE CLIENT / ARCHITECT PRIOR TO THE COMMENCEMENT OF WORK

DRAWING BY:
Alan Meredith
Architectural Services & Epa Percolation Testing
Old Grange, Monasterevin, Co. Kildare
[redacted]

FOR JOSEPH HEFFERNAN,
TULLY EAST,
KILDARE,
Co. KILDARE

SCALE: AS SHOWN | DATE MAR 2026

AGRI SHED PLAN, ELEVATION & SECTION

PROJECT NO.	DRG. NO.	REV.
2026-05	P-01	1

FINANCE CASH OFFICE
Kildare County Council
Áras Chill Dara
Devoy Park
Naas
Co. Kildare
19/03/2026 11:19:02

Receipt No. : FIN1/0/522266
***** REPRINT *****

Joseph Heffernan

PLANNING EXEMPT DEVELOP FEES	80.00
GOODS 80.00	
VAT Exempt/Non-vatable	

Total : 80.00 EUR

Tendered :
Credit Card 80.00
vd
5638

Change : 0.00

Issued By : Margaret Jordan Finance Cash Office
From : Financial Lodgement Area
Vat reg No.0440571C