# Carbury Housing Co. Kildare

Water Supply and Wastewater Management Report

April 2024

2316

Issue No. 1

### **CORA Consulting Engineers**

Behan House, 10 Mount St. Lower Dublin D02HT71 Tel: 01- 6611100

E: info@cora.ie



### **Table of Contents**

1		Introduction	2
	1.1	1 General	2
	1.2	Proposed Water Services Summary	2
2		Wastewater Discharge	2
3		Water Supply	2
4		Pre-Connection Enquiry to Uisce Eireann	3
Α	ppe	endix A – Wastewater Treatment for the Site	4

#### 1 Introduction

#### 1.1 General

This report addresses the water supply and wastewater discharge from the proposed domestic development at Carbury Co. Kildare

A description of the proposed development is as follows:

- The construction of a 4 new domestic units on a greenfield site.
- The redevelopment of an existing building on the stie into a new domestic unit.
- All associated site works.

### 1.2 Proposed Water Services Summary

At the present time there are 2 existing buildings on the overall site within client ownership. Both buildings are served with water supply from the Uisce Eireann network on the public road

New connections are proposed to connect the new residential units on the site to the Uisce Eireann Network.

A new specialist designed wastewater treatment system is proposed to serve the 5 no. units within this application and also will serve one other unit should it be connected to this system in the future.

### 2 Wastewater Discharge

Wastewater from the site will be managed by a new wastewater treatment system. This system is designed by a specialist, Wastewater Technical Services Ltd.

Refer to Appendix A for details of the WW treatment system.

The location of the WW treatment is shown on CORA drawing 2316/C002.

### 3 Water Supply

The proposed new water supply will be taken from the local Uisce Eireann network to the new buildings in accordance with UE standards

The water supply layout is shown on CORA drawing 2316/C002.

### 4. Pre-Connection Enquiry to Uisce Eireann

A pre-connection enquiry for the development has been submitted to Uisce Eireann for 5 No Units.

Details received from UE are below:

Patrick Henderson Aras Chill Dara Devoy Park, Naas Kildare W91X77F

17 April 2020

Dear Patrick Henderson.

UISCE EIREANN I IRESTE WATER

Uisce Éireann Besca OP 448 Offig Sheachadta na Cathrach Theas Cathair Charcai

trish Water PO Box 448, South Cky Delivery Office, Cork City.

www.water.ie

Re: Connection Reference No CD\$19001081 pre-connection enquiry - Subject to contract | Contract denied

Connection for Multi/Mixed Use Development of 5 unit(s) at Carbury, Kildare, Kildare.

Irish Water has reviewed your pre-connection enquiry in relation to a water connection at Carbury, Kildare, Kildare. Based upon the details you have provided with your pre-connection enquiry and on the capacity currently available as assessed by Irish Water, we wish to advise you that, subject to a valid connection agreement being put in place, your proposed connection to the Irish Water network can be facilitated.

You are advised that this correspondence does not constitute an offer in whole or in part to provide a connection to any Irish Water infrastructure and is provided subject to a connection agreement being signed at a later date.

A connection agreement can be applied for by completing the connection application form available at www.water.ie/connections. Irish Water's current charges for water and wastewater connections are set out in the Water Charges Plan as approved by the Commission for Regulation of Utilities.

If you have any further questions, please contact us on 1850 278 278 or +353 1 707 2828, 8.00am-4.30pm, Mon-Fri or email newconnections@water.ie. For further information, visit www.water.ie/connections.

Yours sincerely,

M Drofee

Maria O'Dwyer

Connections and Developer Services

### Appendix A – Wastewater Treatment for the Site



# Site Characterisation & Assessment Report

Completed for

Kildare County Council

c/o BF Construction

Site @ Carbury Carbury Co Kildare W91 A9FH

Completed by: Wastewater Technical Services Ltd. Moyglare Rd, Kilcock, Co Kildare. Ph: 01 6287300

# Scope of Report.

The findings of this report are the result of a desk study and geological field interpretation. Interpretations and conclusions included in the report are based on knowledge of the ground conditions following detailed investigations, as well as the regional soils, subsoils and bedrock geology, and the experience of the author. Wastewater Technical Services Ltd has prepared this report in line with the best current practice and with all reasonable skill, care and diligence in consideration of the limits imposed by the survey techniques used and resources devoted to it by agreement with the client. The interpretive basis of the conclusions contained in this report should be taken into account in any future use of this report.

Wastewater Technical Services Ltd accepts no responsibility for any matters arising if any recommendations contained in this document are not carried out, or are partially carried out, without further advice being obtained from Wastewater Technical Services Ltd.



### **APPENDIX B: SITE CHARACTERISATION FORM**

File Reference:
1.0 GENERAL DETAILS (From planning application)
Prefix: First Name: Kildare Co Co Surname:
Address: Site Location and Townland: Carbury, Co. Kildare W91 A9FH
Telephone No: Fax No:
E-Mail:
Maximum no. of Residents: No. of Double Bedrooms: No. of Single Bedrooms:
Proposed Water Supply: Mains Private Well/Borehole Group Well/Borehole
2.0 GENERAL DETAILS (From planning application)
Soil Type, (Specify Type): BminDW - Deep well drained mineral (Mainly basic)
Aquifer Category: Regionally Important Locally Important Lm Poor
Vulnerability:   Extreme   High   ✔   Moderate   Low   High to Low   Unknown
Bedrock Type: Dinantian Upper Impure Limestones
Name of Public/Group Scheme Water Supply within 1 km: TBC
Groundwater Protection Scheme (Y/N): Yes Source Protection Area: SI SO
Groundwater Protection Response: R1
Presence of Significant Sites (Archaeological, Natural & Historical):  None Within 250m
Past experience in the area: Well drained soil with good rates of percolation.
Comments:  (Integrate the information above in order to comment on: the potential suitability of the site, potential targets at risk, and/or any potential site restrictions).

**Note:** Only information available at the desk study stage should be used in this section.

### 3.0 ON-SITE ASSESSMENT

### 3.1 Visual Assessment

Landscape Position:	Flat site in area and flat land
Slope:	Steep (>1:5) Shallow (1:5-1:20) Relatively Flat (<1:20)
Surface Features with	nin a minimum of 250m (Distance To Features Should Be Noted In Metres)
Houses: 2 houses 35m	n to South West, 2 60m South West, 1 100m North West
Existing Land Use:	Agriculture
Vegetation Indicators:	None
Groundwater Flow Dir	rection: Easterly
Ground Condition:	Dry & firm underfoot
Site Boundaries: Po	ost & Wire fence
Roads: R4	402 60m South West, R403 South East
Outcrops (Bedrock Ar	nd/Or Subsoil): None within 250m
Surface Water Pondin	ng: None within 250m Lakes: None within 250m
Beaches/Shellfish: N	lone within 250m Areas/Wetlands: None within 250m
Karst Features: None	within 250m
Watercourse/Stream*	None within 250m
Drainage Ditches*:	None within 250m
Springs / Wells*:	None within 250m
	ve in order to comment on: the potential suitability of the site, potential targets at risk, the suitability of the site to treat the f the proposed system within the site).

<sup>\*</sup>Note and record water level

### **3.2 Trial Hole** (should be a minimum of 2.1m deep (3m for regionally important aquifers))

To avoid any accidental damage, a trial hole assessment or percolation tests should not be undertaken in areas, which are at or adjacent to significant sites (e.g. NHAs, SACs, SPAs, and/or Archaeological etc.), without prior advice from National Parks and Wildlife Service or the Heritage Service.

Depth of trial	hole (m): 2.00											
Depth from ground surface  o bedrock (m) (if present):  Depth from ground surface  to water table (m) (if present):  0.00												
Depth of water ingress:  0.00 Rock type (if present):  Date and time of excavation: 30/11/2018 14:10 Date and time of examination: 05/12/2018 08:15												
Date and time	ate and time of excavation: 30/11/2018 14:10 Date and time of examination: 05/12/2018 08:15											
Depth of P/T Test*	Soil/Subsoil Texture & Classification**	Plasticity and dilatancy***	Soil Structure	Density/ Compactness	Colour****	Preferential flowpaths						
0.1 m	TOPSOIL		Crumb	Firm	Brown	Some rootlets						
0.2 m												
0.3 m 0.4 m												
0.4 m	Sandy CLAY	Threads- 4,5,4 Ribbons- 110, 110,	Massive	Firm	Brown							
0.6 m		100 Dilatent- No										
0.7 m												
0.8 m												
0.9 m												
1.0 m												
1.1 m												
1.2 m												
1.3 m												
1.4 m												
1.5 m												
1.6 m	Gravely SILT/CLAY	Threads - 2,2,3										
1.7 m	Some cobbles	Ribbons - 60,80,80 Dilatent- Difficult	Granular	Soft	Grey							
1.8 m		Justient Junious										
1.9 m												
2.0 m	2.0m Base											
2.1 m 2.2 m												
2.2 III												
2.4 m												
2.4 III												
2.6 m												
2.7 m												
2.8 m												
2.9 m												
3.0 m												
						-						

Likely T value: 20.00 Note: \*Depth of percolation test holes should be indicated on log above. (Enter P or T at depts as appropriate).

\*\* See Appendix E for BS 5930 classification.

<sup>\*\*\* 3</sup> samples to be tested for each horizon and results should be entered above for each horizon.


<sup>\*\*\*\*</sup> All signs of mottling should be recorded.

#### 3.2 Trial Hole (contd.) Evaluation:

1	No water table or mottling noted in the trial hole.

#### 3.3(a) Percolation ("T") Test for Deep Subsoils and/or Water Table

Step 1: Test Hole Preparation




Step 2: Pre-Soaking Test Holes

Date and Time						
pre-soaking started	04/12/2018	13:00	04/12/2018	13:00	04/12/2018	13:00

Each hole should be pre-soaked twice before the test is carried out. Each hole should be empty before refilling.

**Step 3:** Measuring T<sub>100</sub>



If  $T_{100} > 300$  minutes then T-value > 90 – site unsuitable for discharge to ground

If  $T_{100} \le 210$  minutes then go to Step 4;

If  $T_{100} > 210$  minutes then go to Step 5;

**Step 4:** Standard Method (where  $T_{100} \le 210$  minutes)


Step 4. Otal	idald Mei	illoa (vvi	1616 1	00 > 2101111	nutes)							
Percolation Test Hole		1		2				3				
Fill no.	Start Time (at 300 mm)	Finis Time (at 20 mm)	e	∆t (min)	Start Time (at 300 mm)	Finis Time (at 20 mm)	Э	Δt (min)	Start Time (at 300 mm)	Finis Time (at 20 mm)	Э	∆t (min)
1	09:1	10	09:52	42.00	09:1	4	10:02	48.00	09:0	07	09:47	40.00
2	09:5	53	10:40	47.00	10:0	3	10:55	52.00	09:4	18	10:30	42.00
3	10:4	<b>11</b>	11:34	53.00	10:5	6	11:55	59.00	10:3	31	11:20	49.00
Average ∆t Value				47.33				53.00				43.67
Result of Te	Average   [Hole No   st: T =			11.83 (t <sub>1</sub> )	Average . [Hole No.in/25 mm)			<b>13.25</b> (t <sub>2</sub> )	Average [Hole No			<b>10.92</b> (t <sub>3</sub> )
Comments:												
Step 5: Mod	dified Metl	hod (wh	ere T <sub>10</sub>	<sub>o</sub> > 210 mir	nutes)							
Percolation Test Hole No.		1				2				3		
Fall of water	Time	Time	K <sub>6</sub>	T –	Time	Time	K	T –	Time	Time	K <sub>60</sub>	T –

Percolation Test Hole No.		1			2				3			
Fall of water in hole (mm)	Time Factor = T <sub>f</sub>	Time of fall (mins) = T <sub>m</sub>	K <sub>fs</sub> = T <sub>f</sub> / T <sub>m</sub>	T – Value = 4.45 / K <sub>fs</sub>	Time Factor = T <sub>f</sub>	Time of fall (mins) = T <sub>m</sub>	K <sub>fs</sub> = T <sub>f</sub> / T <sub>m</sub>	T – Value = 4.45 / K <sub>fs</sub>	Time Factor = T <sub>f</sub>	Time of fall (mins) = T <sub>m</sub>	K <sub>fs</sub> = T <sub>f</sub> / T <sub>m</sub>	T – Value = 4.45 / K <sub>fs</sub>
300 - 250	8.1				8.1				8.1			
250 - 200	9.7				9.7				9.7			
200 - 150	11.9				11.9				11.9			
150 - 100	14.1				14.1				14.1			
Average T- Value				0.00	T- Value	Hole 1=	(t <sub>2</sub> )	0.00	T- Value	Hole 1=	= (t <sub>3</sub> )	0.00

Result of Test: T =	0.00 (min/25 mm)
Comments:	

### 3.3(b) Percolation ("P") Test for Shallow Soil / Subsoils and/or Water Table

#### Step 1: Test Hole Preparation



Step 2: Pre-Soaking Test Holes

Date and Time						
pre-soaking started	04/12/2018	13:00	04/12/2018	13:00	04/12/2018	

Each hole should be pre-soaked twice before the test is carried out. Each hole should be empty before refilling.

Step 3: Measuring P<sub>100</sub>

Percolation Test Hole No.	1	2	3
Date of test	05/12/2018	05/12/2018	05/12/2018
Time filled to 400 mm	08:40	08:40	08:40
Time water level at 300 mm	09:17	09:09	09:14
Time to drop 100 mm (P <sub>100</sub> )	37.00	29.00	34.00
Average P <sub>100</sub>			33.33

If  $P_{_{100}} > 300$  minutes then P-value >90 – site unsuitable for discharge to ground

If  $P_{100}^{\circ} \le 210$  minutes then go to Step 4;

If  $P_{100} > 210$  minutes then go to Step 5;

**Step 4:** Standard Method (where  $P_{100} \le 210$  minutes)

Percolation Test Hole		1				2	!				3		
Fill no.	Start Time (at 300 mm)	Fin Tim (at 2 mm	ne 200	Δp (min)	Start Time (at 300 mm)	Fin Tim (at 2 mm)	ne 200	Δp (min)	Start Time (at 300 mm)	Fin Tin (at 2 mm	200	Δp (min)	
1	09:	17	09:56	39.00	09:	09	09:40	31.00	09:	14	09:50	36.00	
2	09:	57	10:40	43.00	09:	41	10:17	36.00	09:	51	10:29	38.00	
3	10:4	41	11:26	45.00	10:	18	10:58	40.00	10:	30	11:11	41.00	
Average ∆p Value				42.33				35.67				38.33	
	Average $\Delta p/4 =$ Average $\Delta p/4 =$ Average $\Delta p/4 =$ [Hole No.1] [Hole No.2] [Hole No.3] [9.58] $(p_3)$												
Result of Tes	st: P =			9.69 (mir	n/25 mm)								
Comments:													
Step 5: Moo	lified Met	hod (w	here P <sub>1</sub>	<sub>00</sub> > 210 mi	nutes)								
Percolation Test Hole No.		1				2					3		
Fall of water in hole (mm)	Time Factor = T <sub>f</sub>	Time of fall (mins) = T <sub>m</sub>	K <sub>fs</sub> = T <sub>f</sub> / T <sub>m</sub>	P – Value = 4.45 / K <sub>fs</sub>	Time Factor = T <sub>f</sub>	Time of fall (mins) = T <sub>m</sub>	K <sub>fs</sub> = T <sub>f</sub> / T <sub>m</sub>	P – Value = 4.45 / K <sub>fs</sub>	Time Factor = T <sub>f</sub>	Time of fall (mins) = T <sub>m</sub>	K <sub>fs</sub> = T <sub>f</sub> / T <sub>m</sub>	P – Value = 4.45 / K <sub>fs</sub>	
300 - 250	8.1				8.1				8.1				
250 - 200 200 - 150	9.7				9.7				9.7				
150 - 100	11.9				14.1				11.9				
Average P- Value	P- Value	Hole 1	1= (p <sub>1</sub> )	0.00	P- Value	Hole 1	= (p <sub>2</sub> )	0.00		e Hole	1= (p <sub>3</sub> )	0.00	
Result of Tes	st: P =			0.00	(min/25 i	mm)							
Comments:													

# 3.4 The following associated Maps, Drawings and Photographs should be appended to this site characterisation form.

- 1. Discovery Series 1:50,000 Map indicating overall drainage, groundwater flow direction and housing density in the area.
- 2. Supporting maps for vulnerability, aquifer classification, soil, bedrock.
- 3. North point should always be included.
- 4. (a) Sketch of site showing measurements to Trial Hole location and
  - (b) Percolation Test Hole locations,
  - (c) wells and
  - (d) direction of groundwater flow (if known),
  - (e) proposed house (incl. distances from boundaries)
  - (f) adjacent houses,
  - (g) watercourses,
  - (h) significant sites
  - (i) and other relevant features.
- 5. Cross sectional drawing of the site and the proposed layout should be submitted.
- 6. Photographs of the trial hole, test holes and site (date and time referenced).

<sup>&</sup>lt;sup>1</sup> The calculated percolation area or polishing filter area should be set out accurately on the site layout drawing in accordance with the code of practice's requirements.

### **4.0 CONCLUSION of SITE CHARACTERISATION**

Integrate the information from the desk study and on-site assessment (i.e. visual assessment, trial hole and percolation tests) above and conclude the type of system(s) that is (are) appropriate. This information is also used to choose the optimum final disposal route of the treated wastewater.

Not Suitable for Development	
Suitable for <sup>1</sup> 1. Septic tank system (septic tank and percolation area)  Yes	Discharge Route  Discharge to Ground Water
2. Secondary Treatment System	
a. septic tank and filter system constructed on-site and polishing filter; or	
b. packaged wastewater treatment system and polishing filter Yes	
5.0 RECOMMENDATION	
Propose to install:	
and discharge to: Ground Water	
Trench Invert level (m):	
Site Specific Conditions (e.g. special works, site improvement works testing e	tc.
This test was carried out as a feasibility measure to see if the site is suitable for discharge to ground No Population equivalent was provided.	ind.
The site is suitable for discharge to ground of treated effluent from a Septic tank or Sewage treatr	nent system.
Any designs should be based on a T Value of 12 and no water table or mottling was found above	2m BGL.
The polishing filter is to be located a minimum of 30m from any well, 10m from any ditch, 10m from any trees.	m the house , 3m from boundary and 4m
Only grey and foul water should enter the sewage treatment system. Rainwater & Storm water sh	ould be directed to soak pits.

<sup>&</sup>lt;sup>1</sup> note: more than one option may be suitable for a site and this should be recorded

<sup>&</sup>lt;sup>2</sup> A discharge of sewage effluent to "waters" (definition includes any or any part of any river, stream, lake, canal, reservoir, aquifer, pond, watercourse or other inland waters, whether natural or artificial) will require a licence under the Water Pollution Acts 1977-90. Refer to Section 2.6.2.

### **6.0 TREATMENT SYSTEM DETAILS**

SYSTEM TYPE: Seption	Tank Syste	m							
Tank Capacity (m³)		Percolation Area			Mounded Percolation Area				
		No. of Trenches			No.	of Trench	es		
		Length of Trenche	es (m	1)	Lenç	gth of Tre	nches (m)		
		Invert Level (m)			Invert Level (m)				
SYSTEM TYPE: Secon	ndary Treatm	nent System							
Filter Systems						Packa	ge Treat	ment S	Systems
Media Type	Area (m²)*	Depth of F	ilter	Invert Level		Type			
Sand/Soil						Streaml	ine BAF Sys	stem	
Soil						Capaci	ty PE		
Constructed Wetland						Sizing	of Primar	y Com	partment
Other								m³	
SYSTEM TYPE: Tertian	ry Treatment	System							
Polishing Filter: Surface	ce Area (m²)*	*	Pa	ickage Treatmer	nt Sys	stem: Ca	pacity (pe	e)	
or Gravity Fed:			Co	onstructed Wetla	nd: S	Surface A	rea (m²)*		
No. of Trenches									
Length of Trenches (m) Invert Level (m)									
DISCHARGE ROUTE:									
Groundwater 🗸	Hydrai	ulic Loading Rate	* (I/n	n².d)					
Surface Water **	Discha	arge Rate (m³/hr)							
TREATMENT STANDA	ARDS:								
Treatment System Perf	ormance Sta	andard (mg/l) B	OD	SS	NH	<sub>4</sub> - N	Total N	То	otal P
As per IS EN12566-3 & S.R.	66 2015								
QUALITY ASSURANCE	E:								
Installation & Commiss	ioning			On-going Mainter	nance	)			
Sepcon Moyglare Road Kilcock Co. Kildare				Sepcon Moyglare Road Kilcock Co. Kildare					

 $<sup>\</sup>ensuremath{^{\star}}$  Hydraulic loading rate is determined by the percolation rate of subsoil

<sup>\*\*</sup> Water Pollution Act discharge licence required

### 7.0 SITE ASSESSOR DETAILS


Company:	Waste Water Technical Services Ltd	
Prefix:	Mr. First Name: Ken Sur	name: Lannery
Address:	Moyglare Road Kilcock, Co. Kildare	
Qualification	ions/Experience: QQI Site Suitability for Waste Water Treatment	
Date of Re	eport: 17/12/2018	
Phone: 08	087 2889381 Fax: N/A	e-mail wastewaterts@gmail.com
Indemnity I	Insurance Number: PI/C/12392/18/1	
Signature:		

# **Supporting Documentation**


- 1. Aquifer Category Map
- 2. Bedrock Type Map
- 3. Soil Type Map
- 4. Groundwater Vulnerability Map
- 5. Site Location & Groundwater Direction
- 6. Photos of test holes & trial hole
- 7. Site Specific Report for proposed sewage system & percolation




### Kildare Co Co - W91 A9FH - Aquifer Map



# Geological Survey Ireland





Map Centre Coordinates (ITM) 670,925 735,041 12/6/2018. 10:33:12 AM

Ordnance Survey Ireland Licence No. EN 0047216 © Ord nance Survey Ireland/Government of Ireland  $\ensuremath{\texttt{©}}$  Geological Survey Ireland/Government of Ireland

### **Bedrock Aquifer**

- Rkc Regionally Important Aquifer -Karstified (conduit) Rkd - Regionally
- Important Aquifer -Karstified (diffuse) RK - Regionally
- Important Aquifer -Karstified Rf - Regionally
- Important Aquifer -Fissured bedrock Lm - Locally Important Aquifer -
- Bedrock which is Generally Moderately Productive
  - Lk Locally Important Aquifer - Karstified
- LI Locally Important Aguifer - Bedrock which is Moderately Productive only in Local Zones PI - Poor Aquifer -Bedrock which is
- Generally Unproductive except for Local Zones Pu - Poor Aquifer -
- Bedrock which is Generally
- Unproductive Lake


Scale: 1:50,000

**PSI Licence** 

This map and its data may not be used or reproduced for commercial purposes without the prior written permission of Copyright holders This map is a user generated static output from an Internet mapping site and is for general reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable



### Kildare Co Co - W91 A9FH - Bedrock Map



Scale: 1:50.000 Geological Survey Ireland



Map Centre Coordinates (ITM) 670,925 735,041 12/6/2018. 4:00:19 PM

© Ord nance Survey Ireland/Government of Ireland © Geological Survey Ireland/Government of Ireland Legend

Outcrop

### Generalised Bedrock (Rock Unit Groups)

Basalts & other Volcanic rocks Permo-Triassic

Sandstones Permo-Triassic

Mudstones and

Gypsum Westphalian

Sandstones Westphalian Shales

Namurian Shales Namurian

Sandstones Namurian

Undifferentiated Dinantian Shales and

Limestones Dinantian Mixed

Sandstones, Shales

and Limestones Dinantian

Sandstones Dinantian Pure

Bedded Limestones Dinantian Upper

Impure Limestones Dinantian

Dolomitised

Limestones Dinantian Pure

Unbedded

Limestones Dinantian Lower

Impure Limestones Dinantian (early)

Sandstones, Shales

and Limestones Dinantian Mudstones and Sandstones

(Cork Group) Devonian Kiltorcan-

type Sandstones

Devonian Old Red Sandstones Granites & other

Igneous Intrusive rocks

Silurian

Metasediments and

Volcanics Ordovician

Metased iments Ordovician Volcanics Cambrian

Metasediments Precambrian

Quartzites. Gneisses

& Schists Precambrian Marbles


PSI Licence

This map and its data may not be used or reproduced for commercial purposes without the prior written permission of Copyright holders This map is a user generated static output from an Internet mapping site and is for general reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable

Ordnance Survey Ireland Licence No. EN 0047216




### Kildare Co Co - W91 A9FH - Groundwater Map



Scale: 1:50,000 Geological Survey Ireland

PSI Licence



Map Centre Coordinates (ITM) 670,925 735,365 12/6/2018, 4:08:13 PM

Ordnance Survey Ireland Licence No. EN 0047216
© Ordnance Survey Ireland/Government of Ireland
© Geological Survey Ireland/Government of Ireland

### Groundwater Vulnerability

X - Rock at or near surface or Karst

E - Extreme

H - High

M - Moderate

L - Low


W - Water

This map and its data may not be used or reproduced for commercial purposes without the prior written permission of Copyright holders. This map is a user generated static output from an Internet mapping site and is for general reference only.


Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.



### Kildare Co Co - W91 A9FH - Subsoil Map



Scale: 1:50.000 Geological Survey Ireland



Map Centre Coordinates (ITM) 670,925 735,041 12/6/2018. 4:02:07 PM

Ordnance Survey Ireland Licence No. EN 0047216 © Ord nance Survey Ireland/Government of Ireland © Geological Survey Ireland/Government of Ireland

### Teagasc Soils

- AminDW Deep well drained mineral (Mainly acidic) AminPD - Mineral
- poorly drained (Mainly acidic) AminPDPT - Peaty
- poorly drained mineral (Mainly acidic) AminSW - Shallow
- well drained mineral (Mainly acidic) AminSP - Shallow
- poorly drained mineral (Mainly acidic) AminSPPT - Shallow
- peaty poorly drained mineral (Mainly
- acidic) AminSRPT Shallow, rocky, peaty/non-
- peatymi... complexes (Mainly acidic)
- BminDW Deep well drained mineral (Mainly basic) BminPD - Mineral
- poorly drained (Mainly basic) BminPDPT - Peaty
- poorly drained mineral (Mainly
- basic) BminSW Shallow well drained mineral
- (Mainly basic) BminSP Shallow poorly drained
- mineral (Mainly basic) BminSPPT - Shallow
- peaty poorly drained mineral (Mainly
- basic)

- BminSRPT Shallow. rocky, peaty/nonpeatymi... complexes (Mainly basic)
- BktPt Blanket peat FenPt - Fen peat RsPt - Raised Peat Cut -
- Cutover/cutaway
- peat AlluvMIN Alluvial (mineral) AlluvMRL - Alluvial
- (marl) Lac Lacustrine type soils
- Scree Scree AeoUND - Aeolian undifferentiated MarSands - Marine
- sand and gravel MarSed -
- Marine/estuarine sediments
- Made Made ground Water - Water
- Unclass

PSI Licence

This map and its data may not be used or reproduced for commercial purposes without the prior written permission of Copyright holders This map is a user generated static output from an Internet mapping site and is for general reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable












T2

T3









# Dámhachtain Breisoideachais agus Oiliúna Further Education and Training Award

## TEASTAS CUSPÓRA SHAINIÚIL LEIBHÉAL 6 LEVEL 6 SPECIFIC PURPOSE CERTIFICATE

in

# Oiriúnacht Suíomh Láithreáin i gcomhair Cóireáil Fuoilluisce Site Suitability for Wastewater Treatment

le Tuillteanas with Merit

Bronnta ar Awarded to

### **KENNETH LANNERY**

ar on

14 Deireadh Fómhair 2018 14 October 2018

Príomhfheidhmeannach Chief Executive

> FET Creidiúntí/Credits 10 NFQ Leibhéal/Level 6 EQF Leibhéal/Level 5





established 1980

Date:

04/09/2018

Our Ref:

WAST03

#### **COVER NOTE**

#### To whom it may concern

Our Client: Address: Waste Water Technical Services Ltd Moyglare Road, Kilcock, Co. Kildare

We act as insurance brokers for the above named client and are pleased to confirm that the following insurance cover is currently in force:

**Professional Business:** 

Percolation Testing & as described in proposal form dated

23/8/18 for the purposes of insurance.

#### **Professional Indemnity Insurance Policy**

Insurance Company:

Lloyds

Policy Number:

TBA

Renewal Date:

31st August 2019

Limit of Indemnity:

€ 1,000,000

Excess:

€ 1,500

Territorial Limits:

Worldwide Excluding USA/Canada

All cover is subject to insurers policy terms, conditions and exclusions, a copy of which are available on request.

This letter is provided as a courtesy to our client as a matter of information only and confers no rights to the holder. We accept no duty of care or responsibility to any third party. This letter does not purport to set out all of the policy terms, conditions and exclusions. Full policy terms, conditions & exclusions are available on request.

Yours sincerely,

Michelle Kavanagh

Certified Insurance Practitioner
E: michelle.kavanagh@mib.ie

Michelle Koosog

PH: 049 4327083





Kilmore Business Park Dublin Road Cavan T: +353 (0) 49 433 2944

E:

W: www.martininsurance.ie E: info@martininsurance.ie










Kildare Co. Co . Carbury Site

		Per Pers	on / Per day	Totals - Per Day		
QTY	Source	Litres	BOD5 grams	Litres	BOD5 grams	
	Domestic					
	1 Bed House / Apartment = 4 PE	150	60	0	0	
2	2 Bed House / Apartment = 4 PE	150	60	1200	480	
2	3 Bed House / Apartment = 5 PE	150	60	1500	600	
	4 Bed House / Apartment = 6 PE	150	60	0	0	
	5 Bed House / Apartment = 7 PE	150	60	0	0	
	Industrial					
	Office and/or factory without canteen	30	20	0	0	
	Office and/or factory with canteen	60	30	0	0	
	Open industrial site e.g quarry (excluding canteen)	40	25	0	0	
	Schools					
	Staff - Non- residential with cooking on site	60	30	0	0	
	Staff - Non- residential with no canteen	40	20	0	0	
	Pupils - Non- residential with cooking on site	60	30	0	0	
	Pupils - Non- residential with no canteen	40	20	0	0	
	Boarding school: (I) residents	180	20	0	0	
	day staff (includes mid-day meal)	60	20	0	0	
	Hotels	00	20			
	Guests	250	75	0	0	
		180	45	0	0	
	Guests (no meals)	+	+	0	0	
	Resident staff	180	60		_	
	Day staff	60	30	0	0	
	Conference	40	20	0	0	
	Restaurant full meals:			0	0	
	(I) luxury catering	25	25	0	0	
	(II) prepared catering	15	15	0	0	
	(III) snack bars	10	10	0	0	
	(IV) function rooms incl. buffets	10	10	0	0	
	(V) fast food	10	10	0	0	
	Pubs & Clubs					
	Residents	200	60	0	0	
	Day staff	60	30	0	0	
	Bar drinkers	10	10	0	0	
	Bar meals	10	10	0	0	
	Amenity Sites					
	Restaurants	15	15	0	0	
50	Function rooms	10	10	500	500	
	Toilet blocks (per use)	5	10	0	0	
	Toilet blocks (long stay car parks)	10	15	0	0	
	Golf clubs	20	10	0	0	
	Squash, with club house	25	15	0	0	
	Swimming	10	10	0	0	
	Football club	30	20	0	0	
	Caravan Sites:	30	20		•	
	(I) Touring	50	35	0	0	
	(II) Static not serviced	75	35	0	0	
	(III) Static fully serviced	150		0	0	
			55			
	(IV) Tent sites	50	35	0	0	
	Hospitals  Peridential address and a second	250			_	
	Residential elderly people	250	60	0	0	
	Residential elderly people plus nursing	300	65	0	0	
	Nursing homes (convalescent)	350	75	0	0	
				Litres	BOD5 gran	
		Cumi	<b>Cumulative Totals</b>		15	
		Population Equivalent		<b>3200</b> 21	2	
		Populat	ion Equivalent	21		
					28	





Moyglare Rd, Kilcock,Co Kildare

Ph: 01 6287300 Email: info@sepcon.ie

Web:www.sepcon.ie

This drawing is Copyright to Ryan Civil Contracting Ltd t/a Sepcon.

#### Notes:


- 1. Drawings for illustration purposes only. Do not scale from this drawing.
- Always refer to the site characterisation report for water invert level and further design info
- Ryan Civil Contracting Ltd t/a Sepcon assume no responsibility for any errors or ommissions in this drawing.

Project Name: 210m<sup>2</sup> Pressurised Soil Polishing Filter

Drawing Title: STR-PB210

Address: Project No: Client Ref:

Date:OCT 2016 Scale: N.T.S Rev. no: Dwg No.





Moyglare Rd, Kilcock,Co Meath Ph: 01 6287300

 $\underline{\textbf{Email:}} \text{ info@sepcon.ie Web:www.sepcon.ie}$ 

This drawing is Copyright to Ryan Civil Contracting Ltd t/a Sepcon

#### Notes

- 1. Do not scale from this drawing.
- 2. Drawings are for illustration purposes only and are subject to change.
- 3. Observe all safety regulations in regard to excavation and lifting requirements.
- 4. Never leave tank lids uncovered or unattended at any time.
- 5. Refer to the site specific report for details of loadings and further design infomation.
- 6. The cross section drawing above shows the tanks in a straight series configuration only. Consult us for excavation requirements in different tank configurations.
- 7. Ground conditions for tank installation to be approved by clients engineer.

Project Name: Streamline Waste Water Treatment System

Drawing Title:PE28 Sewage Treatment System - EN12566-3 & S.R.66:2015

Address: Project No: Client Ref:

Date:OCT16 Scale: N.T.S Rev. no: Dwg No:STR-WWTS-PE28