


GUIDELINES FOR MANAGING OPENINGS IN PUBLIC ROADS

GENERAL REINSTATEMENT NOTES:

1. COMPLIANCE WITH THESE DRAWINGS AND DETAILS ARE MANDATORY. DEPENDENT ON CIRCUMSTANCES AND WHERE DRAWINGS PROVIDE OPTIONS/ALTERNATIVES, ROAD AUTHORITIES MAY SPECIFY ONE OPTION ONLY AS BEING APPLICABLE. WHERE A UTILITY HAS AN APPROVED EQUIVALENT DETAIL FOR BEDDING AND SURROUND THIS MAY BE SUBSTITUTED FOR BEDDING AND SURROUND DETAIL SHOWN IN THE STANDARD DRAWINGS, PROVIDED IT IS AGREED WITH THE ROAD AUTHORITY IN ADVANCE.
2. FULL WIDTH/LANE/BAY REINSTATEMENTS WORKS SHALL BE MACHINE LAID WITH MATERIALS USED IN ACCORDANCE WITH TII SPECIFICATION FOR ROAD WORKS AND USE MATERIALS AND DEPTHS OF RECONSTRUCTION TO MATCH THE EXISTING SURFACE. NOTE: SURFACE DRESSING DOES NOT CONSTITUTE FULL WIDTH REINSTATEMENT UNLESS THE STRUCTURAL ASPHALTIC CONCRETE (AC) LAYER IS PROVIDED OVER THE FULL WIDTH.
3. ON APPROACH TO THE WORKS SITE, THE NAME OF THE CONTRACTOR AND LICENCE HOLDER MUST BE CLEARLY DISPLAYED WITH A 24 HOUR CONTACT NUMBER.
4. ALL WORKS SHALL HAVE A TEMPORARY TRAFFIC MANAGEMENT PLAN, WHICH SHALL BE AVAILABLE FOR INSPECTION ON SITE, AND SHALL COMPLY WITH THE TRAFFIC SIGNS MANUAL AND HEALTH AND SAFETY REQUIREMENTS.
5. PRIOR TO ANY EXCAVATION WORKS TAKING PLACE, THE LOCATION OF ALL UNDERGROUND AND OVER GROUND SERVICES MUST BE IDENTIFIED AND MARKED BY A COMPETENT PERSON TRAINED IN THE USE OF CAPABLE DETECTORS. CONTACT SHALL BE MADE WITH ALL RELEVANT SERVICE PROVIDERS IN THIS REGARD .
6. ALL WORKS AND MATERIALS SHALL COMPLY WITH THE TII SPECIFICATION FOR ROAD WORKS. SERIES 900 OF THAT SPECIFICATION WILL BE THE MARCH 2011 VERSION. ALL OTHER SERIES WILL BE TO THE CURRENT VERSION.
7. EXCAVATION ON A ROAD SHOULD NOT BE CLOSER THAN 500MM TO THE KERB LINE IN ORDER TO PREVENT UNDERMINING OF THE ADJACENT FOOTWAY. THE TRENCH SHOULD BE LOCATED SO AS TO AVOID SURFACE JOINTS BEING LOCATED IN THE WHEEL TRACK AS FAR AS REASONABLY PRACTICABLE.
8. ALL BOUND (OR CONCRETE) EDGES SHALL BE SAW CUT TO EXPOSE THE FULL VERTICAL THICKNESS OF EACH LAYER PRIOR TO EXCAVATION. ALL EDGES SHALL BE ESSENTIALLY STRAIGHT, SMOOTH AND VERTICAL.
9. EXCAVATIONS SHALL BE SUFFICIENTLY PROTECTED TO AVOID HARMFUL EFFECTS CAUSED BY WEATHER OR ADJACENT WHEEL LOADING.
10. REFER TO CHAPTER 6 FOR REQUIREMENTS ON PIPE/DUCT TYPE/COLOUR AND MARKER TAPE.
11. THE METHOD OF WORK SHALL ENSURE PROPER COMPACTION AND SUCH COMPACTION MAY BE TESTED BY THE ROAD AUTHORITY. TO ENSURE ADEQUATE COMPACTION, MINIMUM CLEARANCE MUST BE MAINTAINED VERTICALLY AND HORIZONTALLY BETWEEN INDIVIDUAL DUCTS OR SERVICES INSTALLED IN A GROUP.
12. CL. 808 TO BE USED WITHIN 500MM OF CEMENT BOUND MATERIALS, CONCRETE PAVEMENTS, CONCRETE STRUCTURES OR CONCRETE PRODUCTS. OTHERWISE CL. 804 MAY BE USED. FOAMED CONCRETE TO CL. 1043 MAY ONLY BE USED AS A BEDDING MATERIAL OR BACKFILL MATERIAL WITH PRIOR APPROVAL OF THE ROAD AUTHORITY. CEMENT BOUND GRANULAR MIXTURE B SHALL HAVE A MINIMUM STRENGTH CLASS OF C8/10 , UNLESS OTHERWISE DIRECTED.
13. WHERE STEEL PLATES OR OTHER TRENCH COVERS ARE USED,THEY MUST COMPLY WITH SECTION 6.3.7.
14. HAND LAYING OF HOT BITUMINOUS MIXTURES SHALL BE RESTRICTED TO THE FOLLOWING CIRCUMSTANCES:
 - I. AT THE EDGES OF THE LAYERS OF MATERIAL AND AT GULLIES, MANHOLES AND OTHER IRONWORK
 - II. IN CONFINED SPACES WHERE IT IS IMPRACTICABLE FOR A PAVER TO OPERATE.
 - III. AT APPROACHES TO EXPANSION JOINTS AT BRIDGES, VIADUCTS OR OTHER STRUCTURES.
 - IV. TRANSVERSE REINSTATEMENTS LESS THAN 4 METRES IN WIDTH.
 - V. LONGITUDINAL REINSTATEMENTS LESS THAN 20 METRES IN LENGTH.
 - VI. SURFACE COURSE REINSTATEMENTS OF LONGITUDINAL EXCAVATION LESS THAN 1 METRE IN WIDTH.
 - VII. TEMPORARY REINSTATEMENT. THE METHOD OF LAYING SHALL BE SUCH THAT THE FINISHED SURFACE IS FREE FROM DRAGGING, TEARING AND SEGREGATION OF THE MATERIAL.
15. ALL SURFACE COURSE AGGREGATE SHALL HAVE A MINIMUM PSV OF 60 DECLARED UNLESS OTHERWISE SPECIFIED BY THE ROAD AUTHORITY. TEMPORARY SURFACES TO BE MANAGED IN ACCORDANCE WITH RLS8/2007.
16. ANY DAMAGE TO THE ROAD STRUCTURE OR AREAS ADJACENT TO THE OPENING AND RESULTING FROM THE WORKS SHALL BE REPAIRED AND INCLUDED WITHIN THE AREA TO BE REINSTATED.
17. WHERE THERE ARE EXCEPTIONAL CIRCUMSTANCE NOT COVERED BY THE DRAWING, THE REINSTATEMENT SPECIFICATION MUST BE AGREED WITH THE ROAD AUTHORITY.

FOOTWAYS: ASPHALT CONCRETE (BITUMINOUS MACADAM) PERMANENT REINSTATEMENT




Standard Drawing SD11
SCALE 1:10

NOTES:

Notes 1-17 listed in General Reinstatement Notes apply.

18. All edges shall be cut a minimum of 150mm from sides of excavation.
19. Where a temporary surface has been used material shall be planed out to the depth specified in this drawing. The new permanent surface shall be machine laid and mechanically compacted with a vibrating roller.
20. Clause 808 or cement bound Granular Material surface to be sprayed per Clause 920 prior to application of Asphalt Concrete Layer.
21. Joint sealer to be a hot 50 pen bitumen binder or cold thixotropic bitumen 50 - 70 pen to be applied to all vertical cuts in accordance with B.S. 594987 prior to application of bituminous materials.
22. Joints sealed with hot bitumen and topped with fine sand/grit to get a minimum 55 skid resistance value as determined by the Portable Skid Resistance Pendulum used in accordance with Road Note 27 and shall not exceed 3mm depth and 50mm width.
23. For vehicular accesses the Asphalt Concrete surface shall be 100mm thick. Where the footway may be subjected to heavy loads the asphalt concrete shall be to a depth of 150mm similar to roadway.
24. Accesses to commercial premises require standards detailed in Standard Drawing SD4.
25. Where the trimmed edge of an excavation is within 400mm of a joint/edge, ironwork or other reinstatement, this trimmed edge shall be extended to include same and the area of reinstatement shall be extended accordingly.
26. With footways 1.4m wide or less, full width reinstatement is required. In footways exceeding 1.4m wide, the road authority may approve one additional longitudinal joint.
27. Where works are in close proximity to trees/tree roots compliance with BS 5837:2012 is required. (See Chapter 6)
28. Where a standard depth cannot be met, see detail for protection slab.

FOOTWAYS: CONCRETE PERMANENT REINSTATEMENT



Standard Drawing SD12
SCALE 1:10

NOTES:

Notes 1-17 listed in General Reinstatement Notes apply.

18. Reinforced mesh (A142 or similar approved) shall be used at the discretion of the road authority.
19. Apron to be 150mm thick at driveways and 300mm thick at commercial access areas or where the footway may be subjected to wheel loads.
20. Minimum concrete depth of 150mm may be reduced to 100mm where footway is separated from carriageway by grass verge or by bollards.
21. With footways 1.4m wide or less, full width reinstatement is required. In footways exceeding 1.4m wide, the road authority may approve one additional longitudinal joint.
22. For transverse openings, additional area of reinstatement is required to the nearest bay joint. A complete bay shall be reinstated where specified by the road authority.
23. Surface finish to be similar to adjoining areas e.g. Soft brushed, printed pattern etc.
24. Expansion joints in accordance with Clause 1106 to be neatly formed in straight lines, at not greater than 3m centres & arranged to coincide with joints in kerbs. Joints shall be formed by inserting a double layer of roofing felt or other approved material, which shall extend for the full depth of the slab & finished off neatly at the surface.
25. Where the footway is recently constructed (i.e. less than 10 years), the full bay must be replaced.
26. Where the trimmed edge of an excavation is within 400mm of a joint/edge, ironwork or other reinstatement, this trimmed edge shall be extended to include same and the area of reinstatement shall be extended accordingly.
27. Where works are in close proximity to trees/tree roots compliance with BS 5837:2012 is required. (See Chapter 6)
28. Where a standard depth cannot be met, see detail for protection slab.

PLANNING DRAWING.
NOT FOR CONSTRUCTION.
ALL LEVELS GIVEN ARE
RELATIVE TO ORDNANCE DATUM.
THIS DRAWING HAS BEEN ISSUED FOR INFORMATION
PURPOSES ONLY AND MUST NOT BE USED
FOR CONSTRUCTION UNDER ANY CIRCUMSTANCES

- FOR SETTING OUT REFER TO ARCHITECT'S DRAWINGS.
- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER ARCHITECTURAL AND ENGINEERING DRAWINGS AND ALL OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- DO NOT SCALE THIS DRAWING. USE FIGURED DIMENSIONS ONLY.
- NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR STORED IN ANY RETRIEVAL SYSTEM OF ANY NATURE WITHOUT THE WRITTEN PERMISSION OF O'CONNOR SUTTON CRONIN AS COPYRIGHT HOLDER EXCEPT AS AGREED FOR USE ON THE PROJECT FOR WHICH THE DOCUMENT WAS ORIGINALLY ISSUED.

Rev No.	Date	Revision Note	Drn by	Chkd by
P01	15.05.19	SUITABLE FOR INFORMATION	IK	SD
C01	21.10.20	STAGE COMPLETED - ISSUED FOR PLANNING	SMG	AH

Rev No.	Date	Revision Note	Drn by	Chkd by



Head Office,
9 Prussia Street,
Dublin 7,
D07 KT57

TEL +353 (0)1 8682000

e: contactus@ocsc.ie
w: www.ocsc.ie

Dublin | London | Belfast | Galway | Cork | Birmingham



Client:	THE PAUL HOGARTH COMPANY							
Project:	RATHANGAN PUBLIC REALM							
Title:	TYPICAL DETAILS SHEET 2 OF 3							
Code	Originator	Zone	Level	Type	Role	Number	Status	Revision
P293	OCSC	XX	XX	DR	C	2601	A1	C01
Date:	15.05.19 Scale: NTS		@ A1	Drn by: IK	Chkd by: JS	Aprvd by: AH		